

DATE: January 24, 2013
TO: Registered Vendors: Concrete Flatwork at Fuel Dock and Transfer Station
FROM: Nan Balmer, Assistant Town Administrator
RE: Addendum #2 to Invitation for Bid

This Addendum changes the following in the Town's Invitation for Bid:

1. The Bid opening is delayed until Thursday, February 28, 2013 at 2:00 P.M.
2. The section on Pre-Bid Conference is revised as follows:
Pre-bid conference/site visit: Attendance at a pre-bid conference/site visit is encouraged prior to bidding this project to insure full knowledge of the project. The pre-bid conference shall begin at 2 PM on Tuesday, February 5, 2013, and will be held in the DPW office located at 555 Old Orchard Road.
3. Clarification on steel: If the pile of #5 rebar at the DPW is not adequate to complete the job, the Town shall supply any additional #5 rebar. The contractor shall supply all other steel including ties to wire the rebar together. Contractor may use bricks instead of bolsters to support the rebar mat. The contractor shall supply any bricks
4. Clarification on finish: Concrete to have broom finish.
5. Clarification on connection of new fuel pad to slab which supports the tank: existing slab shall be drilled and doweled every 2 feet with # 5 rebar. New concrete fuel pad to be haunched (dove down) to accept the dowels.